

Volume 2

CHAPTER 10

# CBTC in the United States

*Communications-Based Train Control*  
A Comprehensive Guide for US Transit Professionals  
Francisco Wang

# Chapter Overview

---

- Ground CBTC theory in concrete US deployment experience — what worked, what cost more, and what it means
- Six case studies span NYC L Line (2006) through Honolulu Skyline GoA 4 (2023)
- Examine realistic cost escalations, schedule variances, and labor engagement strategies
- Survey emerging projects: WMATA, SEPTA, CTA, and the airport APM sector
- Part IV opening chapter — US Deployment and Case Studies

# US CBTC Deployment Map




Figure 10.1 — Geographic map of current and planned US CBTC deployments.

# 10.1

## **NYC MTA: The L Line — America's CBTC Pioneer**

---

# L Line CBTC Performance Gains

---

**2×**

**capacity**

Peak throughput: 15 → 30 tph

**93-95%**

**OTP**

On-time performance (vs. 85%  
pre-CBTC)

**99%+**

**availability**

System availability post-  
stabilization

# L Line: Challenges & Lessons

---

- Overlay deployment on legacy fixed-block: complex but feasible
  - 3-year testing phase (2006–2009) — budget for extended validation
  - TWU Local 100 labor negotiations concluded 2005 — early, transparent engagement
  - Hurricane Sandy (2012) caused catastrophic tunnel flooding
- Final cost ~\$500M vs. \$340M baseline (+47% overrun)
  - 12–15% energy savings from ATO-optimized speed profiles
  - Mixed-fleet R143/R160 interoperability required extensive work
  - 20-year Siemens partnership (1999–present) critical to success

# US CBTC Deployment Timeline




Figure 10.2 — Timeline of major US CBTC project milestones from 1999 to present.

# 10.2

## NYC MTA — CBTC Expansion Program

---













# NYC CBTC Expansion: Scale & Ambition




---

- 248 miles of route, 472 stations — the largest CBTC capital deployment in US history
- 7 Line (Flushing): 2nd full CBTC deployment, 29 tph, completed November 2018 (Thales SelTrac)
- Queens Boulevard (E, F, M, R): Siemens Mobility, multi-phase deployment through 2030+
- Culver Line (F, G) and 8th Avenue (A, C, E): in design and early construction phases
- Original \$15–30B program projected into the 2040s; 24/7 operations create testing access paradox

# US CBTC Project Comparison Matrix

**FIGURE 10.3**      **U.S. CBTC PROJECT COMPARISON MATRIX**      **CHAPTER 10**

PROJECT	AGENCY	SUPPLIER	GOA	SCOPE (km)	STATUS	YEAR
 NYC L LINE	 MTA	SIEMENS	GoA 2	15 km	 OPERATIONAL	2006–2020
 NYC 7 LINE	 MTA	THALES	GoA 2	10 km	 OPERATIONAL	2017
 HONOLULU	HART	HITACHI	GoA 4	32 km	 OPERATIONAL	2023
 BART TCMP	BART	HITACHI	GoA 2	200 km	 IN PROGRESS	2020–2035
 BALTIMORE	MTA MD	HITACHI	GoA 2	25 km	 TESTING	2020–2026

 **OPERATIONAL**  
System in revenue service
  **IN PROGRESS**  
Implementation underway
  **TESTING**  
Testing and validation phase

**NOTE:** CBTC = Communications-Based Train Control | GoA = Grade of Automation

Figure 10.3 — Comparison matrix of US CBTC project scope, cost, and schedule outcomes.

# NYC MTA CBTC Expansion Map




Figure 10.4 — NYC MTA CBTC expansion program: line-by-line deployment status and timeline.

# 10.3

## San Francisco BART — Train Control Modernization

---

# BART TCMP: Complete System Replacement

---

- 131 miles, 50 stations — full replacement of 1972-era ATC system
- Hitachi Rail STS SelTrac: \$798M design-build contract (Jan 2020)
- Target: 30 tph through Transbay Tube (vs. 24 tph current)
- 8-phase geographic deployment prioritizing simpler corridors first

- Transbay Tube: 4.5-mile underwater tunnel — specialized radio engineering
- Fleet of the Future: 775 new Alstom railcars, CBTC-ready from manufacture
- Original target 2022 → revised to 2029–2032 (realistic for 24/7 operations)
- Lifecycle cost exceeds \$1.5B over 20 years

# BART TCMP Phased Deployment




Figure 10.5 — BART Train Control Modernization Program phased deployment strategy.

# 10.4

## San Francisco Muni: TCUP

---

# Muni TCUP: Hybrid System Retrofit

---

- 71-mile hybrid network: underground subway + at-grade surface streetcar — unique CBTC challenge
- Hitachi Rail STS: ~\$195–220M contract for system-wide replacement
- Central Subway (Phase 1) opened Nov 2022 under production Hitachi CBTC
- Surface operation requires zoned speed control, traffic signal coordination, crossing detection
- Breda LRV retrofit kits + Siemens LRV4 (CBTC-ready) — mixed-fleet transition

# 10.5

## **Baltimore Metro: Bundled Procurement Model**

---

# Baltimore: Single-Vendor Modernization

---

- 15.5-mile single-line system, 14 stations — Hitachi Rail: \$398M combined contract
- 78 new railcars + complete CBTC signaling from one integrator
- Single-prime accountability eliminates inter-vendor finger-pointing
- Co-designed compatibility: vehicles engineered for Hitachi CBTC from inception
- Model for mid-sized agencies with constrained engineering resources

# 10.6

## Other US Systems and Emerging Projects

---

# Emerging US CBTC Landscape


---

- Honolulu Skyline (HART): First US GoA 4 heavy metro, opened June 2023
  - WMATA: 117 miles, 98 stations — planning/vendor-selection phase for CBTC
  - SEPTA: Broad Street Line modernization — CBTC planned late 2020s
  - CTA: Red Line focus, expected RFP within 1-2 years
- Airport APMs: universal GoA 4 CBTC — JFK, SFO, ATL, DEN, MIA
  - Las Vegas Monorail & Miami Metromover: mature GoA 4 operations
  - NYC 2nd Ave Subway Phases 2-4: CBTC-ready infrastructure
  - Federal IJIA funding + aging infrastructure = opportunity and urgency

# US Airport APMs: GoA 4 CBTC Fleet

System	Airport	GoA	Vendor	Headway
JFK AirTrain	New York JFK	4	Bombardier	3-4 min
SFO AirTrain	San Francisco	4	Bombardier	3-5 min
ATL Skytrain	Atlanta	4	Siemens	4 min
Dulles AeroTrain	Washington	4	MHI	3 min
DIA Airport Train	Denver	4	Bombardier	2-3 min
MIA Mover	Miami	4	Bombardier	2-3 min

# US CBTC Cost & Schedule Variance



Note: Route-km based on approximate mainline route length in revenue service.

Sources: Agency publications, project fact sheets, industry reports.

Figure 10.6 — US CBTC project cost escalation and schedule variance comparison.

# Key Takeaways

---

1. CBTC on US revenue lines delivers measurable, sustained benefits — NYC L Line achieved 26–29 tph with 93–95% OTP; the 7 Line reached 29 tph
1. Retrofit of legacy systems is substantially more complex and costly than new-build; BART's 2022 target shifted to 2029–2032 with \$1.5B+ lifecycle cost
1. Phased commissioning and mixed-fleet operation during transition are standard practice across all major US deployments
1. Honolulu Skyline proves GoA 4 is technically viable and operationally sound in the US, establishing regulatory and labor precedent
1. Federal IJJA funding combined with aging infrastructure creates a 5–8 year window for 3–5 major US agencies to enter CBTC revenue service

# End of Chapter 10

Next: **Chapter 11: International Benchmarks with US Relevance**

Questions & Discussion